

ANNEXURE-A

**SCHEDULE OF INTERIOR DECORATION WORKS OF TANTUJA SHOWROOM AT
BARASAT COLONY MORE, P.O- BARASAT, KOLKATA 700124**

Sl. No.	DESCRIPTION	Qty	Unit	Rate (Rs.)	Amount (Rs.)
1	CIVIL WORKS				
2	Removal of rubbish, scarp materials (like plywood, false ceiling, glass etc) from the working site and disposal of the same beyond the compound, in conformity with the Municipal / Corporation Rules for such disposal, loading into truck and cleaning the site in all respect as per direction of Engineer in charge.	4.00	Cu.m.	197.839	791.355
3	Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity)	8.00	Cu.m.	586.115	4,688.923
4	Dismantling all types of masonry excepting cement concrete plain or reinforced, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m. a) In ground floor including roof.	1.50	Cu.m.	532.735	799.102
5	Dismantling all types of plain cement concrete works, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m. In ground floor including roof. (a) upto 150 mm. thick	1.50	Cu.m.	1,119.100	1,678.650
6	Dismantling all types of existing rolling shutter, furniture, glass, false ceiling, electrical wiring etc. as per the direction of Engineer-in- Charge and stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m. a) In ground floor including roof.	25.00	Sq.m	174.003	4,350.070
7	Stripping off worn out plaster and raking out joints of walls, ceilings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed.	25.00	Sq.m.	22.644	566.105
8	Anti-termite treatment to the junction of wood work and masonry walls with chemical emulsion by admixing chloropyrofos emulsifiable concentrates (1% concentration) with water by weight including spraying at the points of contact with the adjoining masonry by drilling 6m. dia holes at a downward angle of about 45 degree at the junction of woodwork and masonry and squirting chemical emulsion into these holes at the rate of half litre per hole. The entire work is to be carried out as per specification of Code I.S.-6313 (Part-III)-1981. The shutters are to be sprayed with emulsion. on both sides. All wooden fixtures like almirahs, racks etc. are also to be throughly sprayed with chemical emulsion.(Payment will be made on the basis of outside measurements of doors and windows)	76.00	Sq.m.	72.700	5,525.185
9	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]. (i) With 1:6 cement mortar, (b) 25 mm thick plaster	25.00	Sq.m.	219.291	5,482.280
10	Rendering the surface of walls and ceiling with white cement based wall putty of approved make and brand (1.5mm thick)	65.00	Sq.m.	145.400	9,450.974
11	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface to receive decorative textured(matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface throughly, complete as per manufacturer's specification and as per direction of the EIC - Two Coats (In ground floor)	25.00	Sq.m.	53.750	1,343.755

Sl. No.	DESCRIPTION	Qty	Unit	Rate (Rs.)	Amount (Rs.)
12	Protective and Decorative Textured exterior high class matt finish paint of approved quality, composed of special Thermoplastic Resin containing fine crystalline additives derive from Granite as per manufacturer's specification and as per direction of EIC to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer- Two Coats (In Ground floor)	25.00	Sq.m.	120.372	3,009.295
13	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface throughly, complete as per manufacturer's specification and as per direction of the EIC - Solvent based interior grade Acrylic Primer	90.00	Sq.m.	57.802	5,202.207
14	Applying Acrylic Emulsion Paint of approved make and brand on walls and ceiling including sand papering in intermediate coats including putty (to be done under specific instruction of Superintending Engineer) : (Two coats) - Luxury Quality	90.00	Sq.m.	83.426	7,508.340
15	Ordinary Cement concrete (mix 1:1.5:3) with graded stonechips (20 mm nominal size) excluding shuttering and reinforcement if any, as per relevant IS codes- Pakur Variety (in ground floor)	2.50	Sq.m.	6,100.000	15,250.000
16	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in Ground Floor.	2.00	Sq.m.	848.562	1,697.123
17	Supplying and laying true to line and level vitrified tiles of approved brand (size not less than 600 mm X 600 mm X 10 mm thick) in floor, skirting etc. set in 20 mm sand cement mortar (1:4) and 2 mm thick cement slurry back side of tiles using cement @ 2.91Kg./sqM or using polymerised adhesive (6 mm thick layer applied directly over finished artificial stone floor / Mosaic etc without any backing course) laid after application slurry using 1.75 Kg of cement per sqM below mortar only, joints grouted with admixture of white cement and colouring pigment to match with colour of tiles / epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials,labour and all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in- Charge.(White cement, synthetic adhesive and grout material to be supplied by the contractor. With application slurry @1.75 kg/ Sq.m, 20 mm sand cement mortar (1:4) & 2 mm thick cement slurry at back side of tiles, 0.2 kg/ Sq.m white cement for joint filling with pigment. Light Colour - Ground floor Base price should be Rs. 60/- per sq.ft. Sample/colour/design to be approved.	42.00	Sq.m.	1,506.435	63,270.278
18	Supplying and laying true to line and level High Grip, Scratch resistant, Neutral to UV rays, Full Body Vitrified Tiles conforming to IS:15622-2006 & IS 4457-2007 and tested in accordance with IS:13630 [Non-modular sizes for tiles with Skid resistance: 0.6, Mohr's hardness > 7.0, Staining resistance: Class- 1, Water Absorption E < 0.5%] & MOR > 35N/sq.mm and Breaking strength > 1500 N for Outdoor area of building e. g. Gang-way, Corridor, Driveway, Parking lots, Courtyards, Sloping ramps, Entrance lobbies, Patios, Portico etc. set over necessary underlay and 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg./Sqm, joints grouted with admixture of white cement and colouring pigment to match with colour of tiles and removal of wax coating of top surface of tiles with warm water and cleaning the tiles using soft and dry cloth complete including the cost of materials, labour and all other incidental charges complete including backside slurry but excluding the cost of underlay and true to the manufacturer's specification and direction of Engineer-in- Charge. In Ground Floor: Sizes-300 mm x 300 mm x10 mm, Base price should be Rs. 45/- per	5.00	Sq.m.	935.563	4,677.815

Sl. No.	DESCRIPTION	Qty	Unit	Rate (Rs.)	Amount (Rs.)
19	Supplying, fitting & fixing granite slab 15mm to 18mm thick in floor, lobby, stair, landing and treads etc. over 20mm (avg) thick base of cement mortar (1:2) laid with white cement slurry @ 4.40Kg per Square meter before placing of granite and jointed with white cement slurry @ 2.0 Kg per square meter with necessary pigments and complete as per direction of Engineer-in-charge including cost of all materials, labours, curing and roughening of concrete surface complete. In ground floor, (b) Area of each Granite slab above 1.00 Square meter. Base price should be Rs. 180/- per sq.ft. Sample/colour/design to be approved.	2.00	Sq.m.	3,229.778	6,459.556
20	Washing and cleaning with soap water and rubbing with oil cloth in all types of floor, dado & glass.	62.00	Sq.m.	7.151	443.350
21	Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	35.00	Sq.m.	34.562	1,209.677
22	Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : On steel or other metal surface : With super gloss (hi-gloss) - Two coats (with any shade except white)	35.00	Sq.m.	94.152	3,295.327
23	Supplying, fitting & fixing Zn-Al alloy (55% Al & 45% Zn) coating of 150 grams per sq. metre (followed by colour coated on both side) steel sheet work having minimum yield strength of 550 Mpa of trapizoidal profile of approved make (excluding the supporting frame work) fitted and fixed with 55 mm & 25 mm self tapping screw, EPDM Washer 16 mm dia & 3 mm th. washer etc. complete with 150 mm end lap and one corrugation minimum side lap. (Payment to be made on area of finished work). With 0.50 mm thick sheet	10.00	Sq.m.	1,067.853	10,678.528
24	M.S. structural works with hollow sections (square or rectangular shape) conforming to IS: 806-1968 & IS:1161-1998) connected to one another with bracket, gusset, cleat as per design, drawing & direction of Engineer-in-Charge complete including cutting to requisite shape & size, fabrication including metal arc welding conforming to IS: 816-1969 & IS: 9595 using electrodes of approved make and brand conforming to IS:814- 2004, haulage, hoisting and erection all complete. The rate includes the cost of all M.S. Hollow section, all consumables such as electrodes, gas and hire charges of all tools and plants and labour required for execution and all incidental chages (such as electricity, labour insurance) etc. complete. Payment to be made on the basis of calculated weight of structural memebres of MS Holow Section as specified in relevent IS code in finished work. Payment for gusset, bracket, cleat may be made by adding the actual weight of such items with weight of finished structural members. The rates are considered for a hight of erection 8 m. / 2nd floor level from the ground. Add 1.5 % extra over the rate for each additional floor or 4m. beyond the initial 8 m. or part	0.10	MT	89,924.885	8,992.489
25	Supplying fitting and fixing G.I. rolling shutter with 18 B.G .of approved type steel to the section 75mm wide, fitted with coil wire spring to necessiate the fitting of required Nos. of C.I. Pulleys on heavy type solid drawn seamless steel tube complete with locking arrangements both inside and outside specially builtup side guide channels including providing a hood for the steel rolling shutter in the room, painting two coats of approved aluminium paint over a coat of red lead primer complete.	7.00	Sq.M.	3,376.37	23,634.586
26	Oiling and greasing of rolling shutter and repair to in side lock.	10.00	Sq.M.	73.00	730.000
27	Renewing profile of rolling shutter including fitting fixing complete as per existing size and shape.	50.00	Mtr.	54.00	2,700.000

Sl. No.	DESCRIPTION	Qty	Unit	Rate (Rs.)	Amount (Rs.)
28	Renewing spring of rolling shutter as per existing size and shape including fitting fixing complete.	8.00	Nos.	609.00	4,872.000
29	Supplying, fitting and fixing PVC pipes of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, longscrew, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials and two coats of painting with approved paint in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accessories, specials. Payment for painting will be made separately) (a) For Exposed Work, PVC Pipes 100 mm dia.	6.00	Mtr	423.089	2,538.534
30	INTERIOR & FURNITURE WORKS				-
31	Providing and fixing 12mm thick frameless toughened glass door shutter of approved brand and manufacture, including providing and fixing top & bottom pivot & double acting hydraulic floor spring type fixing arrangement and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer in charge (Door handle, lock and stopper etc. to be paid separately)	23.00	Sq.ft	834.260	19,187.980
32	Providing and fixing Glass Door bottom corner patch lock with strike plate of SS finish and aluminium alloy base material casting, Dead bolt projection of 15 mm (single throw) and SS-304 cover of DORMA/DORSET/GODREJ make for 12mm thick frameless toughened glass door shutter including making necessary holes etc. for fixing required fittings, all complete as per direction of Engineer in charge.	1	Each	3,515.810	3,515.810
33	Supplying, fitting & fixing Stainless Steel 'D' or 'H' type of size 300 mm x 19 mm tubular Handle with Grade 304, CE certified, marked & conforming to EN -1154, of approved quality of reputed brand as per direction of Engineer-in-Charge fitted and fixed complete including all incidental charges.	2	Each	1,872.318	3,744.636
34	Providing and fixing in position fixed glass partition work with 12 mm thick clear toughened glass conforming to IS: 2553 (Part-I) with SS-304 patch fittings approved by Engineer-In-charge, Weather Silicone sealant for filling the groove line between glasses or any other surface material for facial work. Work to be done as per design-detail and direction and all approved accessories required to complete the work in all respect.	222	Sq.ft.	506.515	1,12,446.330
35	Providing and fixing 12 mm thick clear glass shelf with edges round off, supported on SS-304 brackets complete fixed with 40 mm long SS screws, rawl plugs etc., as per direction of Engineer-in-charge (Glass area shall be measured for payment).	140.00	Sq.ft.	256.237	35,873.180
36	Providing and fixing in position of glass for cash counter (Top surface) with 12 mm thick clear toughened glass conforming to IS: 2553 (Part-I) with SS-304 patch fittings approved by Engineer-In-charge, Weather Silicone sealant for filling the groove line between glasses or any other surface material for facial work. Work to be done as per design-detail and direction and all approved accessories required to complete the work in all respect.	15.00	Sq.ft.	476.720	7,150.800
37	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing.	2	Sq.m.	2,562.370	5,124.740

Sl. No.	DESCRIPTION	Qty	Unit	Rate (Rs.)	Amount (Rs.)
38	Supplying, fitting and fixing in position of ladder for hanging display of superior grade Stainless Steel 304 material made with hollow sections for hanging clothes as per design-drawing and direction.	10	Kg	536.310	5,363.100
39	Supplying, fitting and fixing boiling water resistant ply conforming to IS: 303- 1989 bonded with phenol formaldehyde synthetic resin of approved make and brand fitted and fixed as per design as per approval and direction of Engineer-in- Charge.[excluding the cost of supporting frame work and teak wood batten/Lipping] , In Ground Floor				-
40	(i) 6mm	10	Sq. M	1,100.031	11,000.314
41	(ii) 12mm	35	Sq. M	1,537.422	53,809.770
42	(iii) 19mm	135	Sq. M	2,229.858	3,01,030.803
43	Supplying fitting, fixing decorative lamination conforming to IS: 2046 : 1995 as per approved make, brand, finish and thickness with fitting, fixing the same on Particle/MDF / Ply Boards with recommended / approved adhesive with proper clipping the sides for better attachment as per direction of Engineer-incharge. The rate includes the cost of labour, adhesive and all incidental charges thereof. In ground floor. Thickness of laminate 1.5mm. Sample/colour/design to be approved.	132	Sq. M	955.824	1,26,168.715
44	Supplying, fitting and fixing CNC cutting jali design as per approved design, made of 17 mm thick water plastic composites (WPC) board with premium quality polished, conforming to IS: 303- 1989 bonded with phenol formaldehyde synthetic resin of approved make and brand fitted and fixed as per direction of Engineer-in- Charge.[excluding the cost of supporting frame work and teak wood batten/Lipping] , Sample/colour/design to be approved.	50	Sq. Ft.	244.319	12,215.950
45	Supplying, fitting & fixing of drawer channels made of Stainless Steel (grade-304) in all respect as per approval and direction of Engineer-in-Charge.	10	R.Ft.	506.515	5,065.150
46	Supplying, fitting & fixing of Godrej drawer lock lock with 3 nos keys in all respect as per approval and direction of Engineer-in- Charge.	6	Each	214.524	1,287.144
47	Supplying PVC rollers for sliding windows as per direction of Engineer in charge.	120	Each	16.685	2,002.224
48	Supplying fitting, fixing Vinyl sheet as per approved write-up, graphics & design, brand, finish and thickness with fitting, fixing the same on Particle/MDF / Ply Boards with recommended / approved adhesive with proper clipping the sides for better attachment as per direction of Engineer-incharge. The rate includes the cost of labour, adhesive and all incidental charges thereof. In ground floor. Sample/colour/design to be approved.	25	Sq. Ft.	107.262	2,681.550
49	Supplying & fixing of Female Mannequin White Gloss, ABS body in all respect as per approval and direction of Engineer-in- Charge. Sample/colour/design to be approved.	2	Each	10,130.300	20,260.600
50	Supplying fitting, fixing of S.S. (grade 304) barrel / tower / socket bolt (full covered) of approved manufactured from extruded section conforming to I.S. 204/74 fitted and fixed with cadmium plated screws	4	Nos.	148.975	595.900
51	Supplying fitting, fixing of S.S. (grade 304) D-type handle of approved quality manufactured from extruded section conforming to I.S. specification (I.S. 230/72) fitted and fixed complete: (vii) 100 mm grip x 8 mm dia rod.	24	Nos.	178.770	4,290.480

Sl. No.	DESCRIPTION	Qty	Unit	Rate (Rs.)	Amount (Rs.)
52	Supplying fitting, fixing of S.S. (grade 304) auto hinges of approved quality manufactured from extruded section conforming to I.S. specification (I.S. 205/66) and fitted and fixed with cadmium plated screws	36	Nos.	143.016	5,148.576
53	Providing and fixing false ceiling on frame work made of special sections, power pressed from M.S. Sheet and galvanized with zinc coating of 150 gms/sqm as per IS: 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37 mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50 mm long with 6 mm dia bolts, other flange of cleat fixed to the angle hangers of size 25 x 10x 0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I, channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I.intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall / partition with the help of rawl plugs at 450 mm centre, with 25 mm long dry wall screws @230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacture's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels	25	Sq.m.	1,145.320	28,632.995
54	Providing and fixing exterior quality Aluminium Composite Panel (ACP) wall cladding on existing Al. /MS frame work with GI brackets, ACP fixed on the existing frame work by folding the edges of ACP panel (Engraving the rear surface of ACP sheet) with CP angles, cleats and stainless Steel screws forming grooves at the periphery of ACP panel. Such grooves filled with foam and silicon sealant etc. complete with all materials (but including the cost of silicon sealant), labour, scaffolding and all other incidental charges complete in all respect as per specification and direction of Engineer-in-charge. (Mode of payment is on finished surface area of ACP) - 3mm thick (0.25mm Al.+2.5mm LDPE +0.25mm Al. PVDF coating) Sample/colour/design to be approved.	22	Sq.m.	2,372.874	52,203.224
55	Supplying and fitting of decorative wall paper as per the direction of Engineer-in- Charge , Sample/colour/design to be approved.	52	Sq. Ft.	47.672	2,478.944
56	Supply of door mat as per approval and direction of Engineer-in-Charge.	20.00	Sq.ft.	95.344	1,906.880
57	Supplying and fitting of S.S. (grade 304) Ring for hanging of sarees, 150 mm dia all complete as per the direction of Engineer-in- Charge	4.00	Each	178.770	715.080
58	Supplying & fixing stool made of wrought iron with nickel finish framing including side & back half round design with cushion all complete. Sample/colour/design to be approved.	4.00	Each	2,621.960	10,487.840
59	Supplying & fixing Executive Chair (Manager) made of wrought iron powder coated framing including side & back half round design with cushion all complete. Sample/colour/design to be approved.	1.00	Each	4,171.300	4,171.300
60	ELECTRICAL WORKS				-

Sl. No.	DESCRIPTION	Qty	Unit	Rate (Rs.)	Amount (Rs.)
61	New electrical wiring for light/plug point with M.S switch board with pp cover fitted with brass screw, PVC(I.S.I mark) conduit pipe, finolex P.V.C 3/22 copper wire, modular switch, socket, 63 Amp change over switch, Main switch 63Amp. (Havels / Siemens), M.C.B of required Amp. In each circuit (each circuit consist of 6 to 8 nos. point), 20 Amp. M.C.B for each A.C machine, 15 Amp.plug point with 5 in 1 plug socket with 15 Amp. Modular switch on M.S box & 3 in 1 plug socket with base. Additional Generator line for required no. of points, distribution main line will be of 7/20 copper wire all complete.	75.00	Each	691.244	51,843.300
62	Supplying and fixing double door 4 Way Horizontal TPN MCB Distribution board with IP-42/43 protection, concealed in wall after cutting the wall & mending good the damages to original finish incl. Inter connection with suitable size of copper wire and neutral link & provision for earthing attachment having following Incoming and outgoing: i) 415V. 63A. 4 Pole Isolator as incomer ii) 250V. 6-32A, C-Curve, SP MCB - 12 nos. for outgoing (Make: Legrand/ ABB Elegance)	1.00	Each	7,296.200	7,296.200
63	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor,single core cable in surface/recessed medium class PVC conduit as required. 2 X 6 sq. mm + 2 X 6 sq. mm	10.00	Rm	523.200	5,232.002
64	Supplying fitting & fixing of Recessed 24 watt LED down lighter as per approval and direction of Engineer-in- Charge. Sample/colour/design to be approved.	70.00	Nos.	1,400.365	98,025.550
65	Supplying fitting & fixing of aluminium Profile (19mm x 8mm) with Led Strip Light, 15watt per mtr with 5amp Driver/Power Supply for 5m led strip . Sample/colour/design to be approved.	10.00	Mtr	592.325	5,923.246
66	Supplying fitting & fixing of wall mount fan 16 inches sweep door as per approval and direction of Engineer-in- Charge. .	3.00	Each	2,979.500	8,938.500
67	Supplying fitting & fixing 1.5 TR Split type, Copper Coil) 5 star rated Air conditioning machine with cord less remote, North west starter, Inverter all complete including copper & drainage pipe line up to 20 feet, power supply cable, civil works etc.in all respect as per direction of Engineer-in- Charge. Sample/colour/design to be approved.	2.00	Nos.	65,549.000	1,31,098.000
68	Providing and fixing ABC dry type fire extinguisher, consisting of welded MS cylindrical body, squeeze, lever discharge valve, fitted with internal discharge tube, high pressure discharge hose, discharge nozzle, suspension bracket, finished externally with red enamel paint and fixed to wall with brackets with rawl plug/dash fasteners complete with internal charge . Capacity 4 kg ISI marked.	3.00	Nos.	2,979.500	8,938.500
69	Supplying fitting & fixing 4 mm. thick korean acrylic lettering, Height - 1.5 or 2 feet as per TANTUJA design (Letter & Logo) including light elating Dion type illumination,driver/ power supply etc. in all complete as per the direction of the EIC. (Letter measurement shall be considered of width or height, which is more.) Sample/colour/design to be approved.	105.00	R.Inch	154.934	16,268.070
70	Supplying fitting & fixing 4 mm. thick korean acrylic solid lettering as per TANTUJA design in all complete as per the direction of the EIC. (Letter measurement shall be considered of width or height, which is more.) Sample/colour/design to be approved.	120.00	R.Inch	83.426	10,011.120
71	Supply, installation, testing & Commissioning of Dome Audio- Video Camera of 2 MP resolution upto 20 m IR distance (Night Vision), HD, 0.1 Lux and F 1.2 lens having 3.6 mm focal length. Sample/colour/design to be approved.	4	Nos.	3,813.760	15,255.040

Sl. No.	DESCRIPTION	Qty	Unit	Rate (Rs.)	Amount (Rs.)
72	Supply, installation, testing & Commissioning of 4 channel stand alone metal body DVR with audio HD for 2 MP, supported upto 4 MP camera, H.264 video compression and CIF resolution recording, single SATA port with following configuration including required supporting stand for keeping DVR - . HDMI & VGA output at resolution . Dual- stream & real-time messaging protocol	1	Nos.	9,296.040	9,296.040
73	Supply installation and configuration of 1 TB Surveillance hard disk drive in Digital video Recorder with minimum spin speed 5400 rpm, SATA interface.	1	Nos.	5,005.560	5,005.560
74	Supply & Fixing 19" LED anti- glare monitor with VGA, HDMI port with all accessories.	1	Nos.	9,176.860	9,176.860
75	Providing & fixing 10A, 12V metal body SMPS for dome cameras.	1	Nos.	2,207.214	2,207.214
76	Wiring in PVC medium duty conduits in surface for CCTV Surveillance System with CCTV copper cable (3+1) FR-PVC with CU alloy braiding.	40	M	85.810	3,432.384
77	Supply & Fixing BNC jack for CCTV cameras.	8	Nos.	67.933	543.461
78	Supply & Fixing male DC jack with high gauge wire for CCTV cameras	4	Nos.	39.329	157.318
79	TOTAL AMOUNT INCLUDING 18% GST & 1% CESS				14,28,054.000

**APPROVED MAKE LIST OF METARIALS FOR INTERIOR DECORATION WORKS OF TANTUJA SHOWROOM AT
BARASAT COLONY MORE, P.O- BARASAT, KOLKATA 700124**

Sl. No.	Materials Description	Make
1	Antitermite treatment	Sika/Cico/Dr.fixit
2	Cement (OPC-43 grade / PPC)	Ultratech/ Birla Uttam/ Binani/ Ambuja/ ACC
3	White Cement & Wall putty	Birla/ JK
4	M.S. Grill & Signage Frame work	TATA/ SAIL/ RINL/ IISCO/Jindal
5	Primer, synthetic enamel paint, Exterior grade Acrylic primer, Textured exterior high class matt finish paint, Interior grade Acrylic Primer, Interior Acrylic Emulsion Paint.	Asian Paints / Nerolac/Dulux/Berger
6	vitriified tiles of approved brand (size not less than 600 mm X 600 mm X 10 mm thick)	Johnson/RAK/ Kajaria
7	Clear Glass & Mirror	Modi guard/ Saint Gobain/Asahi
8	Patch lock with strike plate	DORMA/DORSET/GODREJ/ARCHIS
9	Handle, bracket, Patch fittings, hinge, drawer channels etc. Grade 304	Godrej , Hettich, Dorset
10	Display horizontal ladder (2'x8') of superior grade Stainless Steel 304	TATA/ SAIL/ Jindal/JSW
11	Boiling water resistant ply	Kitply/Green/Century
12	Decorative laminate	Greenlam/Merino/ Sunmica/ Century
13	Adhesive	Fevicol/Vamicol
14	Executive Chair & Stool made of wrought iron powder coated	Raj & Raj / GODREJ
15	Aluminium frame for False ceiling	Hindalco / Jindal / Nalco/ Alom
16	Gypsum for False ceiling	Gyproc/Armstrong/SHERA
17	Aluminium Composite Panel	VIVA/ALUDECOR/ EUROBOND/ALSTRONG
18	Modular Switch, Switch board, plug Socket & accessories	MK / HAVELLS /Anchor Roma
19	Distributions Board (Double Door & Metal Clad Socket Outlet)	HAGER / MDS (Legrand) / MERLIN GERIN/L&T/Siemens
20	RCCB / MCB	HAGER / MDS (Legrand) / MERLIN GERIN
21	PVC Conduit (ISI)	POLYPACK / PRECISION / AKG/Polycab/Finolex/Supreme
22	Electrical Wire	Havells/Polycab/ Finolex
23	LED light, LED strip	jaquar / Philips / Wipro
24	Wall mount fan	Khaitan/Crompton/Havells
25	CCTV Wire	Honeywell/ Finolex / Hikvision
26	BNC Jack	JAM / Advision/ Triplett

Note:

1. Any other material required for the job but not included in the above list shall be executed with prior approval of Engineer-Incharge.
2. The bidder shall quote rates for the various items after ascertaining the availability, delivery schedule etc. of the same.